



NOTES:

1. PRIOR TO PAVING, CONTRACTOR MUST SCHEDULE WITH CITY TO TEST WIRE FOR ELECTRICAL CONTINUITY.
2. INSTALL ELECTRICAL WATER TIGHT CONNECTORS (GEL PACKS) THAT SNAP TOGETHER AT ALL SPLICES.



TRACER WIRE INSTALLATION (NON- METALLIC WATER MAINS)

PUBLIC WORKS ENGINEERING

APPR. BY: PKR

DATE: 03.2018

DRAWN BY: EY

DWG: W12

CAD FILE: 2012_W12_03_2018